



Preliminary
Drainage Report
For

Homewood Mountain Resort

Placer County, California

Prepared for:

JMA Ventures LLC
11025 Pioneer Trail, Suite 101-B
Truckee, CA 96161

Prepared by:



1885 S. Arlington Avenue, Suite 111
Reno, NV 89509
(775) 329-4955

Submitted to:

Placer County Community Development Resource Agency
Engineering and Surveying Department

December 2010

Preliminary Drainage Report for:

Homewood Mountain Resort
Placer County, California

Prepared for:

JMA Ventures LLC
11025 Pioneer Trail, Suite 101-B
Truckee, CA 96161

Prepared by:

Carrie Compton

Jack W. Norberg, P.E.

Nichols Consulting Engineers, Chtd.
1885 S Arlington Ave, Suite 111
Reno, NV 89509

December 20, 2010

TABLE OF CONTENTS

1.0 INTRODUCTION	1
1.1 Project Description	1
1.2 Compliance with Regulations and Adopted Plans	3
2.0 HYDROLOGIC AND HYDRAULIC DESIGN CRITERIA	4
2.1 Placer County Design Criteria	4
2.2 Precipitation and Snowmelt	4
2.3 Infiltration	4
3.0 RUNOFF PEAK FLOW	5
3.1 Runoff Peak Flow Analysis	5
3.2 Peak Flow Analysis	6
3.3 Infiltration Volume Analysis	7
3.4 Treatment & Infiltration Area Descriptions	8
4.0 CONCLUSIONS	9
5.0 REFERENCES	10

APPENDICES

APPENDIX A – SWMM SUMMARY TABLE

APPENDIX B – SWMM TABLES

APPENDIX C – FIGURES

FIGURE 1 - VICINITY MAP

FIGURE 2 - EXISTING CONDITIONS WATERSHED AREAS

FIGURE 3 - PROPOSED DEVELOPMENT WATERSHED AREAS

APPENDIX D - ELLIS CREEK CHANNEL ANALYSIS

FIGURE 1 – ELLIS CREEK CHANNEL PLAN & PROFILE

FIGURE 2 – SOUTH BASE STREAM DAYLIGHTING CROSS SECTIONS

FIGURE 3 – SOUTH BASE ELLIS CREEK AREA MAPPING

1.0 INTRODUCTION

This Preliminary Drainage report for the Homewood Mountain Resort in Homewood, Placer County, California was prepared by Nichols Consulting Engineers (NCE) at the request of Placer County Community Development/Resources Agency to evaluate existing and proposed stormwater runoff flows within the developed project area. The criteria set forth in the Placer County Stormwater Management Manual (SWMM) constitute the basis for this drainage report.

1.1 Project Description

1.1.1 Existing Site Context/Conditions:

Existing on-site Land Use(s): Recreation with accessory uses, and seasonal uses. The property is exclusively used for a ski operation along with its accessory food & beverage and rental/retail uses. Seasonal uses include wedding receptions, the Lake Tahoe Music Festival's "Summer Concert Series", and other community events.

Adjacent/Surrounding Land Uses: Predominantly Residential, followed by Commercial/Tourist. Both of these land use designations typically flank the SR89 corridor.

Current Site Details: Total existing coverage on the entire property is +/- 1.8 million sq ft, whereas the base allowable coverage is just over 4 million sq ft. There are no existing Tourist Accommodation Units (TAUs), Residential Units (RUs), or any Commercial Floor Area (CFA) on the property. Parking lots are predominantly paved, with the exception of the Gravel "overflow" Lot at the North base. It is important to note that both the existing North Base and South Base areas are dominated by surface parking.

Natural Features: Include, but aren't limited to Watersheds (Homewood Mountain contains all or a portion of 3 watersheds); Alpine Lakes – such as Quail Lake and more than half of Lake Louise; creeks and associated tributaries – such as Madden, Quail, and Ellis; Mixed-Conifer type forests, all of which are on mountainous terrain ranging from a base elevation of +/-6230 ft to a top elevation of roughly 7800 feet.

1.1.2 Proposed Site Context/Conditions:

North Base: Approximately 56 Residential Condominiums distributed among 4 smaller residential buildings, up to 20 of which are planned to be fractional ownership. The main hotel lodge includes approximately 30 Penthouse Condominium Units (Upper Floors of Hotel), up to 75 Traditional Hotel Rooms, and approximately 40 two-bedroom for sale Condo-Hotel Units. The North Base also includes a request for up to 25,000 sq ft of Commercial Floor Area and up to 13 workforce housing apartments attached to the east and north side of the day skier parking structure.

South Base: Up to 99 Residential Condominiums in a series of 2 full story plus roof-top unit residential buildings are planned for the South Base area. The existing full vehicle shop/maintenance facility at the South Base will be eliminated with servicing of rubber-tire vehicles moved to an off-site location. Snow based equipment maintenance is planned at a new mid-mountain facility. The proposed plan relocates all existing day-skier access to the North Base area helping to further reinforce the sense of a neighborhood residential area. The existing culvert for the Homewood Creek is planned to be removed to allow the stream to be day-lighted and bridged.

Between Base Areas (above Sacramento Avenue): 16 townhomes on the Planned Development lot accessed via Tahoe Ski Bowl Way from the South Base.

Mid-Mountain: The mid-mountain will include a new 15,000+/- sq ft day lodge with a gondola terminal, food & beverage facility, outdoor dining, small sundry outlet, and an outdoor swimming facility for use during the summer months. The new mid-mountain lodge replaces the white tent structure and the existing concrete foundation located near the mid-mountain. The snow based vehicle shop/maintenance facility is proposed to be rebuilt in the mid-mountain area behind the proposed mid-mountain lodge.

Parking at Base Areas: Parking spaces provided at North Base include approximately 300 day skier spaces in a 3 level parking structure, roughly 60 limited surface parking spaces at the retail and day skier drop-off area, and approximately 450 underground parking spaces directly below the building footprint of the hotel/lodge structure. The South Base will include approximately 150 parking spaces directly below the residential building footprints. This takes advantage of the excavation required for the building foundations and allows for more pervious landscape surface around the buildings (in lieu of surface parking).

1.2 Compliance with Regulations and Adopted Plans

This preliminary drainage report was prepared to conform with the Placer County Stormwater Management Manual (SWMM) and the requirements set forth by the Tahoe Regional Planning Agency (TRPA). The proposed drainage facilities and improvements for this project will be designed to meet compliance with the local, state, and regional regulations and adopted plans. The preliminary drainage report shows that proposed conditions mitigated cumulative stormwater flows will be less than existing conditions watershed flows for the 7 analyzed sub-watershed areas.

Construction related detention basins for on-site runoff will be designed as part of the construction SWPPP document.

2.0 Hydrologic and Hydraulic Design Criteria

2.1 Placer County Design Criteria

The storm drainage collection, conveyance and treatment facilities for the proposed project will be designed according to the Placer County Storm Water Management Manual (SWMM), dated September 1, 1990. All existing and proposed watersheds were analyzed using the Small Watershed Peak Flow Worksheet as shown in the included SWMM tables. According to the SWMM, the 10-year event is the minimum design storm for sizing all drainage facilities and all new development shall be planned and designed so that no damages occur to structures or improvements and to prevent loss of life during the 100-year event.

2.2 Precipitation and Snowmelt

Average annual precipitation ranges from 40 to 45 inches per year at the project site elevation. The majority of this precipitation occurs between November and May in the form of snow, which is included in the annual precipitation quantity as equivalent water content.

Though snow predominates the precipitation regime, treatment facilities will be designed using rainfall models.

2.3 Infiltration

Infiltration rates are dependant on soil type and vegetation. For the purpose of this drainage report, infiltration rates between 0.15 to 0.51 inches per hour were selected for each watershed by calculating the percentage of cover type for each soil group and averaging the infiltration rate accordingly. Cover types vary between good cover of woodland consisting of coniferous and broadleaf trees with a canopy density of at least 50% to paved streets and roads with open ditches. Soils of the soil group A have “low runoff potential with high infiltration

rates even when thoroughly wetted and consisting chiefly of deep, well to excessively drained sands and gravel.” Soils of the soil group B have “moderate infiltration rates when thoroughly wetted and consist chiefly of moderately deep to deep, moderately well to well drained soils with moderately fine to moderately coarse textures. These soils have a moderate rate of water transmission” (SWMM, 1990).

3.0 RUNOFF PEAK FLOW

3.1 Runoff Peak Flow Analysis

The runoff flow analysis was conducted according to the computation of peak flows from small watershed outlined in the SWMM. This method allows an evaluation of the peak flow from a small watershed without extensive computation. It may be used to estimate the peak runoff from basins of up to 200 acres, in areas in which no significant ponding occurs.

The method is based on a relationship between the characteristic watershed response time and peak flow per unit area from precipitation patterns typical for the region. The peak flow is a function of the area, unit peak flow, infiltration rate, and impervious surface area and was calculated using the spreadsheet calculations included in this report.

The project area is located at elevations between 6,230 feet and 7,600 feet above sea level (ASL). Snow covered areas are assumed impervious since the ground beneath is likely to be saturated and could also be frozen. The portion of the watershed covered with snow depends on elevation and location relative to the Sierra Nevada crest according to the SWMM. Based on Table 5-4 of the SWMM, 90 percent impervious was selected for the winter peak flow calculations. The summer peak flows were calculated using the actual impervious coverage areas in each watershed for the existing and proposed conditions.

The peak flows for the post-project conditions were developed based on the requirements of the SWWM manual.

3.2 Peak Flow Analysis

The peak flow analysis was conducted by determining the runoff from the proposed layout of the development and drainage facilities. The following table summarizes the calculated peak flows for each watershed area for the existing and proposed development conditions during the summertime.

Summer - Peak Flow Rates Existing Conditions (10-, and 100-year)

WSA	Runoff Area (acres)	10-Year (cfs)	100-Year (cfs)
WSA 1	28.3	20.35	41.26
WSA 2	42.4	27.79	58.31
WSA 3	9.6	4.80	10.48
WSA 4	67.4	21.81	65.61
WSA 5	5.4	4.29	8.61
WSA 6	2.2	2.65	5.10
WSA 7	145.7	97.57	199.55
Totals:	301.0	179.26	388.93

Summer - Peak Flow Rates Proposed Conditions (10-, and 100-year)

WSA	Runoff Area (acres)	10-Year (cfs)	100-Year (cfs)
WSA 1	28.3	18.81	36.96
WSA 2	42.4	23.90	49.02
WSA 3	9.6	5.29	10.77
WSA 4	67.4	21.25	65.34
WSA 5	5.4	4.32	7.47
WSA 6	2.2	2.66	5.00
WSA 7	145.7	97.93	199.91
Totals:	301.0	174.16	374.47

Winter - Peak Flow Rates Existing Conditions (10-, and 100-year)

WSA	Runoff Area (acres)	10-Year (cfs)	100-Year (cfs)
WSA 1	28.3	25.12	46.03
WSA 2	42.4	37.38	67.90
WSA 3	9.6	8.36	14.05
WSA 4	67.4	56.45	100.25
WSA 5	5.4	5.79	10.13

WSA 6	2.2	3.28	5.73
WSA 7	145.7	140.82	242.81
Totals:	301.0	277.21	486.89

Winter - Peak Flow Rates Proposed Conditions (10-, and 100-year)

WSA	Runoff Area (acres)	10-Year (cfs)	100-Year (cfs)
WSA 1	28.3	21.87	40.02
WSA 2	42.4	32.65	57.77
WSA 3	9.6	7.89	13.37
WSA 4	67.4	54.34	98.43
WSA 5	5.4	5.2	8.34
WSA 6	2.2	3.18	5.52
WSA 7	145.7	140.86	242.84
Totals:	301.0	265.98	466.30

3.3 Infiltration Volume Analysis

Table 1 lists the required runoff volume to be stored or infiltrated on site. The proposed Low Impact Development (LID) and infiltration components are designed to store and infiltrate (at a minimum) the runoff generated by the 20-year, 1-hour event calculated at 1 inch over the impervious developed surface area.

Table 1: Impervious Surface Areas and Runoff Volumes

Underground Infiltration Galleries						
	North-1	North-2	North-3	North-4	South-1	South-2
Gallery Type	SW	SW	SW	SW	SW	SW
Total Impervious Area (sf)	24,635	19,890	145,378	174,587	89,307	44,527
Required Infiltration Vol. (cf)	2,053	1,658	12,115	14,549	7,442	3,711
Proposed Gallery volume (cf)	2,681	2,167	15,904	23,441	9,650	8,040
Finish Grade (ft)	6238	6237.5	6238	6240.5	6269	6272
Bottom Elev. of Gallery (ft)	6234	6233	6233.5	6236	6264.5	6267.5
SHGW (ft)	6232	6231	6231.5	6234	6256.5	6263
GW Clearance (ft)*	2	2	2	2	8	4.5
Adjacent GW Monitoring Well Data (well#, SHGW)	MW3N, 6230.7	GP2, 6230.7	GP5, 6230.76	GP8, 6233.58	MW3S, 6256.5	GP4, <66262.93
Infil. Gallery Dimensions (ft)	48x36x3	63x22x3	120x86x3	145x105x2	90x80x2.5	100x52x3
Legend:	<p>Note*</p> <p>SW= stormwater</p> <p>GW= groundwater</p> <p>MW= monitoring well</p> <p>GP= monitoring well</p> <p>Seasonal high groundwater levels are projected to rise 0.7 feet under stormwater galleries & 0.8 feet under groundwater reinjection galleries due to infiltration.</p>					

3.4 Treatment & Infiltration Area Descriptions

In order to meet TRPA requirements for treatment of storm water runoff from impervious surfaces, a series of bio swales, storm drain collection and sub-surface infiltration devices are proposed to be constructed with the development.

The intent of the proposed design is to collect all runoff from impervious areas such as the building roofs, walkways, roadways, and parking areas and convey it to infiltration trenches sized to meet TRPA requirements.

4.0 CONCLUSIONS

Design for the proposed Homewood Mountain Resort project incorporates current requirements by Placer County for storm water collection and conveyance as well as requirements by the TRPA. The SWMM post development calculations show a cumulative reduction in peak flow from existing to proposed conditions for the 10 and 100 year storm events. Therefore the proposed storm drain facilities are designed to capture, convey and infiltrate (at a minimum) runoff generated by the 20-year, 1-hour event at 1 inch over the impervious surface area per TRPA requirements.

The proposed storm drain collection, conveyance and infiltration facilities will comply with the Placer County Storm Water Management Manual (SWMM), dated September 1, 1990.

5.0 REFERENCES

Placer County, Flood Control and Water Conservation District; *Stormwater Management Manual (SWMM)*; September 1990.

United States Forest Service; *Soil Survey Tahoe National Forest Area, California*, January 2002.

DISTRIBUTION

JMA VENTURES LLC

HOMEWOOD MOUNTAIN RESORT

December 20, 2010

Copies 2 Rebecca Taber, Placer County

Copies 1 Melanie Green, HBA

Copies 1 David Tirman, JMA

Copies 1 NCE Project File

QUALITY CONTROL REVIEWER



Paul Pettersen
Principal

Appendix A

SWMM Summary Table

**SWMM Summary Sheet
Summer Impervious Calculations
Homewood Mountain Resort**

Lahontan 20-Yr, 1-Hr Storm Event Calculations

Total Watershed Area (sf)	Impervious Area (sf)	Infiltration Requirement (in)	Required Volume (cf)	Proposed Infiltration Volume (cf)
13,111,354	651,876	0.9	54,324	61,883

Placer County SWMM Model Calculations

	10-YEAR PEAK FLOW			100-YEAR PEAK FLOW		
	Existing Conditions	Proposed Conditions	Exist/Proposed Difference	Existing Conditions	Proposed Conditions	Exist/Proposed Difference*
WATERSHED AREAS	[cfs]	[cfs]	[cfs]	[cfs]	[cfs]	[cfs]
WS-1	20.35	18.81	-1.54	41.26	36.96	-4.30
WS-2	27.79	23.90	-3.89	58.31	49.02	-9.29
WS-3	4.80	5.29	0.50	10.48	10.77	0.29
WS-4	21.81	21.25	-0.57	65.61	65.34	-0.28
WS-5	4.29	4.32	0.03	8.61	7.47	-1.15
WS-6	2.65	2.66	0.01	5.10	5.00	-0.10
WS-7	97.57	97.93	0.37	199.55	199.91	0.37
TOTAL	179.26	174.16	-5.10	388.93	374.47	-14.46

* Negative numbers shown in the tables represent a reduction in flow from existing to proposed conditions.

SWMM Summary Sheet
Winter Impervious Calculations
Homewood Mountain Resort

Lahontan 20-Yr, 1-Hr Storm Event Calculations

Total Watershed Area (sf)	Impervious Area (sf)	Infiltration Requirement (in)	Required Volume (cf)	Proposed Infiltration Volume (cf)
13,111,354	651,876	0.9	54,324	61,883

Placer County SWMM Model Calculations

	10-YEAR PEAK FLOW			100-YEAR PEAK FLOW		
	Existing Conditions	Proposed Conditions	Exist/Proposed Difference	Existing Conditions	Proposed Conditions	Exist/Proposed Difference*
WATERSHED AREAS	[cfs]	[cfs]	[cfs]	[cfs]	[cfs]	[cfs]
WS-1	25.12	21.87	-3.25	46.03	40.02	-6.01
WS-2	37.38	32.65	-4.73	67.90	57.77	-10.13
WS-3	8.36	7.89	-0.47	14.05	13.37	-0.68
WS-4	56.45	54.34	-2.12	100.25	98.43	-1.82
WS-5	5.79	5.20	-0.59	10.13	8.34	-1.78
WS-6	3.28	3.18	-0.10	5.73	5.52	-0.21
WS-7	140.82	140.86	0.03	242.81	242.84	0.03
TOTAL	277.21	265.98	-11.23	486.89	466.30	-20.59

* Negative numbers shown in the tables represent a reduction in flow from existing to proposed conditions.

Appendix B

SWMM Tables

Summer

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-1					
Area (acres)	28.3	Elevation (ft)	6702	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	516	0.23	0.4			13.46
Collector 1	1942	0.38	0.1	20.7	15	3.36
Collector 2	369	0.18	0.05	25.3	15	0.48
Collector 3	221	0.02	0.05	28.3	1	0.37
Total Response Time (minutes)						17.67
Unit Peak Flow (cfs/acre)						0.91
Infiltration Rate (in/hr)					0.17	
Infiltration Factor (cfs/acre)					0.21	
Percent Impervious					8.5	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						20.35

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-2					
Area (acres)	42.4	Elevation (ft)	6645	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.27	0.4			12.63
Collector 1	1853	0.33	0.1	28.2	15	3.12
Collector 2	824	0.07	0.1	37.3	3	1.56
Collector 3	305	0.01	0.05	42.4	1	0.56
Collector 4						
Total Response Time (minutes)						17.88
Unit Peak Flow (cfs/acre)						0.91
Infiltration Rate (in/hr)					0.23	
Infiltration Factor (cfs/acre)					0.3	
Percent Impervious					10	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						27.79

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-3					
Area (acres)	9.6	Elevation (ft)	6593	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.36
Collector 1	1715	0.30	0.1	8.6	15	4.05
Collector 2	280	0.12	0.02	9.6	3	0.19
Collector 3						
Total Response Time (minutes)						18.60
Unit Peak Flow (cfs/acre)						0.91
Infiltration Rate (in/hr)					0.35	
Infiltration Factor (cfs/acre)					0.43	
Percent Impervious					3.8	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						4.80

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-4					
Area (acres)	67.4	Elevation (ft)	6652	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	2448	0.26	0.1	57.5	15	3.81
Collector 2	1456	0.04	0.02	67.4	3	0.92
Collector 3						
Total Response Time (minutes)						18.99
Unit Peak Flow (cfs/acre)						0.90
Infiltration Rate (in/hr)					0.51	
Infiltration Factor (cfs/acre)					0.62	
Percent Impervious					7.3	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						21.81

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-5					
Area (acres)	5.4	Elevation (ft)	7408	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.19	0.4			14.04
Collector 1	616	0.23	0.1	5.4	15	1.81
Collector 2						
Collector 3						
Total Response Time (minutes)						15.85
Unit Peak Flow (cfs/acre)						1.10
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.31	
Percent Impervious					1.0	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						4.29

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-6					
Area (acres)	2.2	Elevation (ft)	7565	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	100	0.30	0.4			4.66
Collector 1	401	0.07	0.1	2.2	15	2.32
Collector 2						
Collector 3						
Total Response Time (minutes)						6.98
Unit Peak Flow (cfs/acre)						1.50
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.31	
Percent Impervious					0.0	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						2.65

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-7					
Area (acres)	145.7	Elevation (ft)	7465	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	4308	0.27	0.1	145.7	15	5.24
Collector 2						
Collector 3						
Total Response Time (minutes)						19.50
Unit Peak Flow (cfs/acre)						1.00
Infiltration Rate (in/hr)					0.28	
Infiltration Factor (cfs/acre)					0.33	
Percent Impervious					1.1	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						97.57

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-1					
Area (acres)	28.3	Elevation (ft)	6702	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	516	0.23	0.4			13.46
Collector 1	1942	0.38	0.1	20.7	15	3.36
Collector 2	1051	0.06	0.025	24.5	1	0.74
Collector 3						
Total Response Time (minutes)						17.56
Unit Peak Flow (cfs/acre)						0.91
Infiltration Rate (in/hr)					0.15	
Infiltration Factor (cfs/acre)					0.18	
Percent Impervious					22.3	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						18.81

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-2					
Area (acres)	42.4	Elevation (ft)	6645	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.27	0.4			12.63
Collector 1	1853	0.33	0.1	28.2	15	3.12
Collector 2	1344	0.05	0.04	33.7	15	2.30
Collector 3	707	0.01	0.025	38.1	1	1.09
Total Response Time (minutes)						19.15
Unit Peak Flow (cfs/acre)						0.89
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.32	
Percent Impervious					18.2	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						23.90

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-3					
Area (acres)	9.6	Elevation (ft)	6593	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.36
Collector 1	1715	0.30	0.1	8.6	15	4.05
Collector 2	527	0.06	0.025	9.1	1	0.47
Collector 3						
Total Response Time (minutes)						18.88
Unit Peak Flow (cfs/acre)						0.90
Infiltration Rate (in/hr)					0.30	
Infiltration Factor (cfs/acre)					0.36	
Percent Impervious					11.5	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						5.29

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-4					
Area (acres)	67.4	Elevation (ft)	6652	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	2448	0.26	0.1	57.5	15	3.81
Collector 2	1456	0.04	0.02	64.8	3	0.93
Collector 3						
Total Response Time (minutes)						19.00
Unit Peak Flow (cfs/acre)						0.90
Infiltration Rate (in/hr)					0.51	
Infiltration Factor (cfs/acre)					0.62	
Percent Impervious					7.6	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						21.25

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-5					
Area (acres)	5.4	Elevation (ft)	7408	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.19	0.4			14.04
Collector 1	631	0.22	0.1	4.8	3	1.32
Collector 2						
Collector 3						
Total Response Time (minutes)						15.36
Unit Peak Flow (cfs/acre)						1.10
Infiltration Rate (in/hr)					0.22	
Infiltration Factor (cfs/acre)					0.26	
Percent Impervious					20.4	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						4.32

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-6					
Area (acres)	2.2	Elevation (ft)	7565	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	180	0.32	0.4			6.52
Collector 1	376	0.30	0.22	2.2	3	1.54
Collector 2						
Collector 3						
Total Response Time (minutes)						8.06
Unit Peak Flow (cfs/acre)						1.45
Infiltration Rate (in/hr)					0.23	
Infiltration Factor (cfs/acre)					0.28	
Percent Impervious					5.9	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						2.66

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-7					
Area (acres)	145.7	Elevation (ft)	7465	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	4308	0.27	0.1	145.7	15	5.24
Collector 2						
Collector 3						
Total Response Time (minutes)						19.50
Unit Peak Flow (cfs/acre)						1.00
Infiltration Rate (in/hr)					0.28	
Infiltration Factor (cfs/acre)					0.33	
Percent Impervious					1.2	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						97.93

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-1					
Area (acres)	28.3	Elevation (ft)	6702	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	516	0.23	0.4			13.46
Collector 1	1942	0.38	0.1	20.7	15	3.36
Collector 2	369	0.18	0.05	25.3	15	0.48
Collector 3	221	0.02	0.05	28.3	1	0.37
Total Response Time (minutes)						17.67
Unit Peak Flow (cfs/acre)						1.65
Infiltration Rate (in/hr)					0.17	
Infiltration Factor (cfs/acre)					0.21	
Percent Impervious					8.5	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						41.26

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
 Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
 Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
 Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-2					
Area (acres)	42.4	Elevation (ft)	6645	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.27	0.4			12.63
Collector 1	1853	0.33	0.1	28.2	15	3.12
Collector 2	824	0.07	0.1	37.3	3	1.56
Collector 3	305	0.01	0.05	42.4	1	0.56
Collector 4						
Total Response Time (minutes)						17.88
Unit Peak Flow (cfs/acre)						1.63
Infiltration Rate (in/hr)					0.23	
Infiltration Factor (cfs/acre)					0.3	
Percent Impervious					10	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						58.31

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-3					
Area (acres)	9.6	Elevation (ft)	6593	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.36
Collector 1	1715	0.30	0.1	8.6	15	4.05
Collector 2	280	0.12	0.02	9.6	3	0.19
Collector 3						
Total Response Time (minutes)						18.60
Unit Peak Flow (cfs/acre)						1.50
Infiltration Rate (in/hr)					0.35	
Infiltration Factor (cfs/acre)					0.43	
Percent Impervious					3.8	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						10.48

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111

Reno, Nevada 89509

(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-4					
Area (acres)	67.4	Elevation (ft)	6652	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	2448	0.26	0.1	57.5	15	3.81
Collector 2	1456	0.04	0.02	67.4	3	0.92
Collector 3						
Total Response Time (minutes)						18.99
Unit Peak Flow (cfs/acre)						1.55
Infiltration Rate (in/hr)					0.51	
Infiltration Factor (cfs/acre)					0.62	
Percent Impervious					7.3	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						65.61

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-5					
Area (acres)	5.4	Elevation (ft)	7408	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.19	0.4			14.04
Collector 1	616	0.23	0.1	5.4	15	1.81
Collector 2						
Collector 3						
Total Response Time (minutes)						15.85
Unit Peak Flow (cfs/acre)						1.90
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.31	
Percent Impervious					0.5	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						8.61

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-6					
Area (acres)	2.2	Elevation (ft)	7565	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	100	0.30	0.4			4.66
Collector 1	401	0.07	0.1	2.2	15	2.32
Collector 2						
Collector 3						
Total Response Time (minutes)						6.98
Unit Peak Flow (cfs/acre)						2.60
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.31	
Percent Impervious					0.0	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						5.10

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
 Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
 Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
 Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Existing Conditions WS-7					
Area (acres)	145.7	Elevation (ft)	7465	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	4308	0.27	0.1	145.7	15	5.24
Collector 2						
Collector 3						
Total Response Time (minutes)						19.50
Unit Peak Flow (cfs/acre)						1.70
Infiltration Rate (in/hr)					0.28	
Infiltration Factor (cfs/acre)					0.33	
Percent Impervious					1.1	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						199.55

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-1					
Area (acres)	28.3	Elevation (ft)	6702	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	516	0.23	0.4			13.46
Collector 1	1942	0.38	0.1	20.7	15	3.36
Collector 2	1051	0.06	0.025	24.5	1	0.74
Collector 3						
Total Response Time (minutes)						17.56
Unit Peak Flow (cfs/acre)						1.65
Infiltration Rate (in/hr)					0.15	
Infiltration Factor (cfs/acre)					0.18	
Percent Impervious					22.3	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						36.96

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-2					
Area (acres)	42.4	Elevation (ft)	6645	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.27	0.4			12.63
Collector 1	1853	0.33	0.1	28.2	15	3.12
Collector 2	1344	0.05	0.04	33.7	15	2.30
Collector 3	707	0.01	0.025	38.1	1	1.09
Total Response Time (minutes)						19.15
Unit Peak Flow (cfs/acre)						1.55
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.32	
Percent Impervious					18.2	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						49.02

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-3					
Area (acres)	9.6	Elevation (ft)	6593	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.36
Collector 1	1715	0.30	0.1	8.6	15	4.05
Collector 2	527	0.06	0.025	9.1	1	0.47
Collector 3						
Total Response Time (minutes)						18.88
Unit Peak Flow (cfs/acre)						1.50
Infiltration Rate (in/hr)					0.30	
Infiltration Factor (cfs/acre)					0.36	
Percent Impervious					11.5	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						10.77

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-4					
Area (acres)	67.4	Elevation (ft)	6652	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	2448	0.26	0.1	57.5	15	3.81
Collector 2	1456	0.04	0.02	64.8	3	0.93
Collector 3						
Total Response Time (minutes)						19.00
Unit Peak Flow (cfs/acre)						1.58
Infiltration Rate (in/hr)					0.51	
Infiltration Factor (cfs/acre)					0.62	
Percent Impervious					7.6	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						65.34

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-5					
Area (acres)	5.4	Elevation (ft)	7408	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.19	0.4			14.04
Collector 1	631	0.22	0.1	4.8	3	1.32
Collector 2						
Collector 3						
Total Response Time (minutes)						15.36
Unit Peak Flow (cfs/acre)						1.75
Infiltration Rate (in/hr)					0.22	
Infiltration Factor (cfs/acre)					0.26	
Percent Impervious					20.4	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						7.47

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-6					
Area (acres)	2.2	Elevation (ft)	7565	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	180	0.32	0.4			6.52
Collector 1	376	0.30	0.22	2.2	3	1.54
Collector 2						
Collector 3						
Total Response Time (minutes)						8.06
Unit Peak Flow (cfs/acre)						2.50
Infiltration Rate (in/hr)					0.23	
Infiltration Factor (cfs/acre)					0.28	
Percent Impervious					5.9	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						5.00

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Summer Calculations					
Watershed	Proposed Conditions WS-7					
Area (acres)	145.7	Elevation (ft)	7465	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	4308	0.27	0.1	145.7	15	5.24
Collector 2						
Collector 3						
Total Response Time (minutes)						19.50
Unit Peak Flow (cfs/acre)						1.70
Infiltration Rate (in/hr)					0.28	
Infiltration Factor (cfs/acre)					0.33	
Percent Impervious					1.2	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						199.91

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Winter

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-1					
Area (acres)	28.3	Elevation (ft)	6702	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	516	0.23	0.4			13.46
Collector 1	1942	0.38	0.1	20.7	15	3.36
Collector 2	369	0.18	0.05	25.3	15	0.48
Collector 3	221	0.02	0.05	28.3	1	0.37
Total Response Time (minutes)						17.67
Unit Peak Flow (cfs/acre)						0.91
Infiltration Rate (in/hr)					0.17	
Infiltration Factor (cfs/acre)					0.21	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						25.12

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
 Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
 Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
 Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-2					
Area (acres)	42.4	Elevation (ft)	6645	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.27	0.4			12.63
Collector 1	1853	0.33	0.1	28.2	15	3.12
Collector 2	824	0.07	0.1	37.3	3	1.56
Collector 3	305	0.01	0.05	42.4	1	0.56
Collector 4						
Total Response Time (minutes)						17.88
Unit Peak Flow (cfs/acre)						0.91
Infiltration Rate (in/hr)					0.23	
Infiltration Factor (cfs/acre)					0	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						37.38

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-3					
Area (acres)	9.6	Elevation (ft)	6593	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.36
Collector 1	1715	0.30	0.1	8.6	15	4.05
Collector 2	280	0.12	0.02	9.6	3	0.19
Collector 3						
Total Response Time (minutes)						18.60
Unit Peak Flow (cfs/acre)						0.91
Infiltration Rate (in/hr)					0.35	
Infiltration Factor (cfs/acre)					0.43	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						8.36

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-4					
Area (acres)	67.4	Elevation (ft)	6652	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	2448	0.26	0.1	57.5	15	3.81
Collector 2	1456	0.04	0.02	67.4	3	0.92
Collector 3						
Total Response Time (minutes)						18.99
Unit Peak Flow (cfs/acre)						0.90
Infiltration Rate (in/hr)					0.51	
Infiltration Factor (cfs/acre)					0.62	
Percent Impervious					90	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						56.45

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-5					
Area (acres)	5.4	Elevation (ft)	7408	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.19	0.4			14.04
Collector 1	616	0.23	0.1	5.4	15	1.81
Collector 2						
Collector 3						
Total Response Time (minutes)						15.85
Unit Peak Flow (cfs/acre)						1.10
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.31	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						5.79

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

90	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-6					
Area (acres)	2.2	Elevation (ft)	7565	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	100	0.30	0.4			4.66
Collector 1	401	0.07	0.1	2.2	15	2.32
Collector 2						
Collector 3						
Total Response Time (minutes)						6.98
Unit Peak Flow (cfs/acre)						1.50
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.31	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						3.28

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-7					
Area (acres)	145.7	Elevation (ft)	7465	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	4308	0.27	0.1	145.7	15	5.24
Collector 2						
Collector 3						
Total Response Time (minutes)						19.50
Unit Peak Flow (cfs/acre)						1.00
Infiltration Rate (in/hr)					0.28	
Infiltration Factor (cfs/acre)					0.33	
Percent Impervious					90	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						140.82

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-1					
Area (acres)	28.3	Elevation (ft)	6702	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	516	0.23	0.4			13.46
Collector 1	1942	0.38	0.1	20.7	15	3.36
Collector 2	1051	0.06	0.025	24.5	1	0.74
Collector 3						
Total Response Time (minutes)						17.56
Unit Peak Flow (cfs/acre)						0.91
Infiltration Rate (in/hr)					0.15	
Infiltration Factor (cfs/acre)					0.18	
Percent Impervious					90	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						21.87

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-2					
Area (acres)	42.4	Elevation (ft)	6645	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.27	0.4			12.63
Collector 1	1853	0.33	0.1	28.2	15	3.12
Collector 2	1344	0.05	0.04	33.7	15	2.30
Collector 3	707	0.01	0.025	38.1	1	1.09
Total Response Time (minutes)						19.15
Unit Peak Flow (cfs/acre)						0.89
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.32	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						32.65

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-3					
Area (acres)	9.6	Elevation (ft)	6593	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.36
Collector 1	1715	0.30	0.1	8.6	15	4.05
Collector 2	527	0.06	0.025	9.1	1	0.47
Collector 3						
Total Response Time (minutes)						18.88
Unit Peak Flow (cfs/acre)						0.90
Infiltration Rate (in/hr)					0.30	
Infiltration Factor (cfs/acre)					0.36	
Percent Impervious					90	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						7.89

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-4					
Area (acres)	67.4	Elevation (ft)	6652	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	2448	0.26	0.1	57.5	15	3.81
Collector 2	1456	0.04	0.02	64.8	3	0.93
Collector 3						
Total Response Time (minutes)						19.00
Unit Peak Flow (cfs/acre)						0.90
Infiltration Rate (in/hr)					0.51	
Infiltration Factor (cfs/acre)					0.62	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						54.34

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-5					
Area (acres)	5.4	Elevation (ft)	7408	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.19	0.4			14.04
Collector 1	631	0.22	0.1	4.8	3	1.32
Collector 2						
Collector 3						
Total Response Time (minutes)						15.36
Unit Peak Flow (cfs/acre)						1.10
Infiltration Rate (in/hr)					0.22	
Infiltration Factor (cfs/acre)					0.26	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						5.20

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-6					
Area (acres)	2.2	Elevation (ft)	7565	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	180	0.32	0.4			6.52
Collector 1	376	0.30	0.22	2.2	3	1.54
Collector 2						
Collector 3						
Total Response Time (minutes)						8.06
Unit Peak Flow (cfs/acre)						1.45
Infiltration Rate (in/hr)					0.23	
Infiltration Factor (cfs/acre)					0.28	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						3.18

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-7					
Area (acres)	145.7	Elevation (ft)	7465	Return Period (years)	10	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	4308	0.27	0.1	145.7	15	5.24
Collector 2						
Collector 3						
Total Response Time (minutes)						19.50
Unit Peak Flow (cfs/acre)						1.00
Infiltration Rate (in/hr)					0.28	
Infiltration Factor (cfs/acre)					0.33	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						140.86

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
 Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
 Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
 Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-1					
Area (acres)	28.3	Elevation (ft)	6702	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	516	0.23	0.4			13.46
Collector 1	1942	0.38	0.1	20.7	15	3.36
Collector 2	369	0.18	0.05	25.3	15	0.48
Collector 3	221	0.02	0.05	28.3	1	0.37
Total Response Time (minutes)						17.67
Unit Peak Flow (cfs/acre)						1.65
Infiltration Rate (in/hr)					0.17	
Infiltration Factor (cfs/acre)					0.21	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						46.03

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-2					
Area (acres)	42.4	Elevation (ft)	6645	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.27	0.4			12.63
Collector 1	1853	0.33	0.1	28.2	15	3.12
Collector 2	824	0.07	0.1	37.3	3	1.56
Collector 3	305	0.01	0.05	42.4	1	0.56
Collector 4						
Total Response Time (minutes)						17.88
Unit Peak Flow (cfs/acre)						1.63
Infiltration Rate (in/hr)					0.23	
Infiltration Factor (cfs/acre)					0	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						67.90

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-3					
Area (acres)	9.6	Elevation (ft)	6593	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.36
Collector 1	1715	0.30	0.1	8.6	15	4.05
Collector 2	280	0.12	0.02	9.6	3	0.19
Collector 3						
Total Response Time (minutes)						18.60
Unit Peak Flow (cfs/acre)						1.50
Infiltration Rate (in/hr)					0.35	
Infiltration Factor (cfs/acre)					0.43	
Percent Impervious					90	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						14.05

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-4					
Area (acres)	67.4	Elevation (ft)	6652	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	2448	0.26	0.1	57.5	15	3.81
Collector 2	1456	0.04	0.02	67.4	3	0.92
Collector 3						
Total Response Time (minutes)						18.99
Unit Peak Flow (cfs/acre)						1.55
Infiltration Rate (in/hr)					0.51	
Infiltration Factor (cfs/acre)					0.62	
Percent Impervious					90	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						100.25

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-5					
Area (acres)	5.4	Elevation (ft)	7408	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.19	0.4			14.04
Collector 1	616	0.23	0.1	5.4	15	1.81
Collector 2						
Collector 3						
Total Response Time (minutes)						15.85
Unit Peak Flow (cfs/acre)						1.90
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.31	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						10.13

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-6					
Area (acres)	2.2	Elevation (ft)	7565	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	100	0.30	0.4			4.66
Collector 1	401	0.07	0.1	2.2	15	2.32
Collector 2						
Collector 3						
Total Response Time (minutes)						6.98
Unit Peak Flow (cfs/acre)						2.60
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.31	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						5.73

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
"Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Existing Conditions WS-7					
Area (acres)	145.7	Elevation (ft)	7465	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	4308	0.27	0.1	145.7	15	5.24
Collector 2						
Collector 3						
Total Response Time (minutes)						19.50
Unit Peak Flow (cfs/acre)						1.70
Infiltration Rate (in/hr)					0.28	
Infiltration Factor (cfs/acre)					0.33	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						242.81

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
 Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
 Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
 Streets and Roads (A = 0.07, B = 0.06).

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-1					
Area (acres)	28.3	Elevation (ft)	6702	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	516	0.23	0.4			13.46
Collector 1	1942	0.38	0.1	20.7	15	3.36
Collector 2	1051	0.06	0.025	24.5	1	0.74
Collector 3						
Total Response Time (minutes)						17.56
Unit Peak Flow (cfs/acre)						1.65
Infiltration Rate (in/hr)					0.15	
Infiltration Factor (cfs/acre)					0.18	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						40.02

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-2					
Area (acres)	42.4	Elevation (ft)	6645	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.27	0.4			12.63
Collector 1	1853	0.33	0.1	28.2	15	3.12
Collector 2	1344	0.05	0.04	33.7	15	2.30
Collector 3	707	0.01	0.025	38.1	1	1.09
Total Response Time (minutes)						19.15
Unit Peak Flow (cfs/acre)						1.55
Infiltration Rate (in/hr)					0.26	
Infiltration Factor (cfs/acre)					0.32	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						57.77

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-3					
Area (acres)	9.6	Elevation (ft)	6593	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.36
Collector 1	1715	0.30	0.1	8.6	15	4.05
Collector 2	527	0.06	0.025	9.1	1	0.47
Collector 3						
Total Response Time (minutes)						18.88
Unit Peak Flow (cfs/acre)						1.50
Infiltration Rate (in/hr)					0.30	
Infiltration Factor (cfs/acre)					0.36	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						13.37

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
Reno, Nevada 89509
(775) 329-4955

**Placer County Flood Control and Water Conservation District
Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-4					
Area (acres)	67.4	Elevation (ft)	6652	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	2448	0.26	0.1	57.5	15	3.81
Collector 2	1456	0.04	0.02	64.8	3	0.93
Collector 3						
Total Response Time (minutes)						19.00
Unit Peak Flow (cfs/acre)						1.58
Infiltration Rate (in/hr)					0.51	
Infiltration Factor (cfs/acre)					0.62	
Percent Impervious					90	
Watershed Peak Flow (cfs): Area x Unit Peak Flow-(1-Percent Impervious) x Area x Infiltration Factor						98.43

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-5					
Area (acres)	5.4	Elevation (ft)	7408	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.19	0.4			14.04
Collector 1	631	0.22	0.1	4.8	3	1.32
Collector 2						
Collector 3						
Total Response Time (minutes)						15.36
Unit Peak Flow (cfs/acre)						1.75
Infiltration Rate (in/hr)					0.22	
Infiltration Factor (cfs/acre)					0.26	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						8.34

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-6					
Area (acres)	2.2	Elevation (ft)	7565	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	180	0.32	0.4			6.52
Collector 1	376	0.30	0.22	2.2	3	1.54
Collector 2						
Collector 3						
Total Response Time (minutes)						8.06
Unit Peak Flow (cfs/acre)						2.50
Infiltration Rate (in/hr)					0.23	
Infiltration Factor (cfs/acre)					0.28	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						5.52

1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5. Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and Streets and Roads (A = 0.07, B = 0.06).

* The last collector area assumes a 50% reduction in the proposed development area due to stormwater runoff that is mitigated by proposed onsite stormwater infiltration devices.

Nichols Consulting Engineers, Chtd.

1885 S. Arlington Ave., Suite 111
 Reno, Nevada 89509
 (775) 329-4955

**Placer County Flood Control and Water Conservation District
 Small Watershed Peak Flow Worksheet**

Date	12/20/2010					
Engineer	Jack Norberg					
Project	Homewood Mountain Resort - Winter Calculations					
Watershed	Proposed Conditions WS-7					
Area (acres)	145.7	Elevation (ft)	7465	Return Period (years)	100	
	Length (ft)	Slope (ft/ft)	Manning's n value	Contributing Area (acres)	Side Slope (ft/ft)	Response Time (minutes)
Overland Flow	500	0.18	0.4			14.26
Collector 1	4308	0.27	0.1	145.7	15	5.24
Collector 2						
Collector 3						
Total Response Time (minutes)						19.50
Unit Peak Flow (cfs/acre)						1.70
Infiltration Rate (in/hr)					0.28	
Infiltration Factor (cfs/acre)					0.33	
Percent Impervious					90	
Watershed Peak Flow (cfs): $\text{Area} \times \text{Unit Peak Flow} - (1 - \text{Percent Impervious}) \times \text{Area} \times \text{Infiltration Factor}$						242.84


1. Manning's n Values taken from Placer County, Storm Water Management Manual (SWMM), Table 5-5.
 Woods with some Underbrush - Low = 0.4

2. Percent Impervious taken from Placer County, Storm Water Management Manual (SWMM), Table 5-4
 "Snow Covered Areas" Elevation 6,500 feet East = 90%

3. Infiltration Rates taken from Placer County, Storm Water Management Manual (SWMM), Table 5-3, for
 Hydrologic Soil Groups with Good Woodland- Coniferous Cover (A = 0.53, B = 0.26, C = 0.15, D = 0.11) and
 Streets and Roads (A = 0.07, B = 0.06).

Appendix C

Figures



VICINITY MAP



**Nichols Consulting
Engineers, Chtd.**
1885 S. Arlington Ave., Suite 111
Reno, NV 89509
(775) 329-4955

**VICINITY/SITE MAP
HOMEWOOD MOUNTAIN RESORT
PLACER COUNTY
CALIFORNIA**

FIGURE

1

DRAWN
CKC


JOB NUMBER
A514.02.14

APPROVED

DATE
DECEMBER 2010


REVISED

DATE



LEGEND	
	FLOW PATH
	WATERSHED BOUNDARY
	CONCENTRATION POINT

	Nichols Consulting Engineers, Chtd.		HOMEWOOD MOUNTAIN RESORT		SHEET
	1885 S. Arlington Ave., Suite 111		EXISTING CONDITIONS		
	Reno, NV 89509		WATERSHED AREAS		2
	(775) 329-4955				
DRAWN	JOB NUMBER	APPROVED	DATE	REVISED DATE	
CKC	A514.02.14		DECEMBER 2010		




LEGEND	
	FLOW PATH
	WATERSHED BOUNDARY
	CONCENTRATION POINT

	Nichols Consulting Engineers, Chtd.	HOMEWOOD MOUNTAIN RESORT PROPOSED DEVELOPMENT WATERSHED AREAS		SHEET 3
	1885 S. Arlington Ave., Suite 111 Reno, NV 89509 (775) 329-4955			REVISED DATE
	DRAWN CKC	JOB NUMBER A514.02.14	APPROVED	DATE DECEMBER 2010

Appendix D


Ellis Creek Channel Analysis




This drawing is the property of NICHOLS CONSULTING ENGINEERS, including all patented and patentable features, and/or confidential information and its use is conditioned upon the user's agreement not to reproduce the drawing, in whole or part, nor the material described thereon, nor the use of the drawing for any purpose other than specifically permitted in writing by NICHOLS CONSULTING ENGINEERS.

DATE: _____


SOUTH BASE ELLIS CREEK CHANNEL PLAN & PROFILE	HOMEWOOD VILLAGE RESORTS, LLC HOMEWOOD VILLAGE RESORTS, LLC P.O. BOX 3938 TRUCKEE, CALIFORNIA 96160	Nichols Consulting Engineers, Chtd. Engineering & Environmental Services 1885 S. Adington Ave., Suite #111 Reno, NV 89509 Ph: (775) 329-0855 Fax: (775) 329-5098	DESIGNED: CXC	REVISIONS			
			DRAWN: CXC	No.	Date	CHKD	APPD
SHEET 1 OF 3			CHECKED: AS				
			JOB No: AS14.02.14				
			SCALE: AS NOTED				
			DATE: 01/04/2011				




CHANNEL CROSS SECTION - STA: 11+00 SECTION 1
MAX. WATER SURFACE ELEV: 6319.97
MAX. WATER VELOCITY: 15.91 ft/s
Q₁₀₀=370 CFS




CHANNEL CROSS SECTION - STA: 12+00 SECTION 2
MAX. WATER SURFACE ELEV: 6306.14
MAX. WATER VELOCITY: 12.11 ft/s
Q₁₀₀=370 CFS




CHANNEL CROSS SECTION - STA: 13+00 SECTION 3
MAX. WATER SURFACE ELEV: 6295.04
MAX. WATER VELOCITY: 7.85 ft/s
Q₁₀₀=370 CFS



CHANNEL CROSS SECTION - STA: 14+00 SECTION 4
MAX. WATER SURFACE ELEV: 6284.57
MAX. WATER VELOCITY: 9.59 ft/s
Q₁₀₀=370 CFS




CHANNEL CROSS SECTION - STA: 15+00 SECTION 5
MAX. WATER SURFACE ELEV: 6269.82
MAX. WATER VELOCITY: 7.16 ft/s
Q₁₀₀=370 CFS




CHANNEL CROSS SECTION - STA: 16+40 SECTION 6
MAX. WATER SURFACE ELEV: 6268.35
MAX. WATER VELOCITY: 8.52 ft/s
Q₁₀₀=370 CFS

Crossing - Proposed Homewood Bridge (bottomless), Design Discharge - 370.0 cfs



CHANNEL CROSS SECTION AT PROPOSED BRIDGE SECTION BRIDGE
HEADWATER ELEV: 6274.02
OUTLET VELOCITY: 9.26 ft/s
TAILWATER VELOCITY: 8.46 ft/s
Q₁₀₀=370 CFS

Crossing - Ex Homewood Creek, Design Discharge - 370.0 cfs
Culvert - Culvert 1, Culvert Discharge - 80.6 cfs




CHANNEL CROSS SECTION AT EXISTING CULVERT SECTION CULVERT
HEADWATER ELEV: 6280.54
OUTLET VELOCITY: 15.919 ft/s
TAILWATER VELOCITY: 10.664 ft/s
Q₁₀₀=370 CFS

FOR REVIEW ONLY
NOT FOR CONSTRUCTION
DATE: 01/04/2011

DATE: _____

This drawing is the property of NICHOLS CONSULTING ENGINEERS, including all patented and patentable features, and/or confidential information and its use is conditioned upon the user's agreement not to reproduce the drawing, in whole or part, nor the material described thereon, nor the use of the drawing for any purpose other than specifically permitted in writing by NICHOLS CONSULTING ENGINEERS.



REVISIONS				
No.	Date	CHKD	APPD	



NOTE
MAPPING & TOPO BY TRISTATE SURVEYING LTD.

This drawing is the property of NICHOLS CONSULTING ENGINEERS, including all patented and patentable features, and/or confidential information and its use is conditioned upon the user's agreement not to reproduce the drawing, in whole or part, nor the material described thereon, nor the use of the drawing for any purpose other than specifically permitted in writing by NICHOLS CONSULTING ENGINEERS.

FOR REVIEW ONLY
NOT FOR CONSTRUCTION
DATE: 01/04/2011



DATE: _____

SOUTH BASE ELLIS CREEK AREA MAPPING		HOMEWOOD VILLAGE RESORTS, LLC HOMEWOOD VILLAGE RESORTS, LLC P.O. BOX 3938 TRUCKEE, CALIFORNIA 96160		Nichols Consulting Engineers, Chtd. Engineering & Environmental Services 1885 S. Arlington Ave., Suite #111 Reno, NV 89509 Ph: (775) 329-0955 Fax: (775) 329-5098		REVISIONS			
						DESIGNED:	CHK	NO.	DATE
SHEET 3 OF 3						DRAWN:	CHK		
						CHECKED:			
						JOB No:	AS 14.02.14		
						SCALE:	AS NOTED		
						DATE:	01/04/2011		

HY-8 Culvert Analysis Report

Table 1 - Summary of Culvert Flows at Crossing: Ex Homewood Creek

Headwater Elevation (ft)	Total Discharge (cfs)	Culvert 1 Discharge (cfs)	Roadway Discharge (cfs)	Iterations
6278.75	60.00	60.00	0.00	1
6279.32	94.00	67.02	26.88	6
6279.53	128.00	69.50	58.40	5
6279.71	162.00	71.54	90.41	5
6279.87	196.00	73.33	122.49	4
6280.01	230.00	74.96	154.92	4
6280.15	264.00	76.47	187.48	4
6280.28	298.00	77.87	219.86	3
6280.41	332.00	79.21	252.63	3
6280.52	366.00	80.49	285.44	3
6280.54	370.00	80.63	289.15	2
6279.00	63.17	63.17	0.00	Overtopping

Rating Curve Plot for Crossing: Ex Homewood Creek

Total Rating Curve
Crossing: Ex Homewood Creek




Table 2 - Culvert Summary Table: Culvert 1


Total Discharge (cfs)	Culvert Discharge (cfs)	Headwater Elevation (ft)	Inlet Control Depth (ft)	Outlet Control Depth (ft)	Flow Type	Normal Depth (ft)	Critical Depth (ft)	Outlet Depth (ft)	Tailwater Depth (ft)	Outlet Velocity (ft/s)	Tailwater Velocity (ft/s)
60.00	60.00	6278.75	3.798	0.0*	5-S2n	1.151	1.964	1.182	0.887	14.253	5.970
94.00	67.02	6279.32	4.368	0.0*	5-S2n	1.234	2.080	1.239	1.154	15.094	6.945
128.00	69.50	6279.53	4.580	0.0*	5-S2n	1.263	2.121	1.270	1.380	15.225	7.684
162.00	71.54	6279.71	4.758	0.0*	5-S2n	1.287	2.155	1.294	1.581	15.352	8.285
196.00	73.33	6279.87	4.917	0.0*	5-S2n	1.308	2.185	1.314	1.762	15.474	8.797
230.00	74.96	6280.01	5.064	0.0*	5-S2n	1.328	2.208	1.333	1.930	15.562	9.243
264.00	76.47	6280.15	5.202	0.0*	5-S2n	1.345	2.225	1.350	2.086	15.650	9.640
298.00	77.87	6280.28	5.331	0.0*	5-S2n	1.362	2.241	1.363	2.233	15.768	9.999
332.00	79.21	6280.41	5.455	0.0*	5-S2n	1.378	2.257	1.378	2.371	15.854	10.327
366.00	80.49	6280.52	5.574	0.0*	5-S2n	1.393	2.271	1.393	2.503	15.913	10.630
370.00	80.63	6280.54	5.588	0.0*	5-S2n	1.395	2.273	1.395	2.518	15.919	10.664

* theoretical depth is impractical. Depth reported is corrected.

Inlet Elevation (invert): 6274.95 ft, Outlet Elevation (invert): 6270.33 ft

Culvert Length: 56.84 ft, Culvert Slope: 0.0816


Culvert Performance Curve Plot: Culvert 1



Water Surface Profile Plot for Culvert: Culvert 1

Crossing - Ex Homewood Creek, Design Discharge - 370.0 cfs

Culvert - Culvert 1, Culvert Discharge - 80.6 cfs



Site Data - Culvert 1

Site Data Option: Culvert Invert Data

Inlet Station: 10.00 ft

Inlet Elevation: 6274.95 ft

Outlet Station: 66.65 ft

Outlet Elevation: 6270.33 ft

Number of Barrels: 1

Culvert Data Summary - Culvert 1

Barrel Shape: Pipe Arch

Barrel Span: 49.00 in

Barrel Rise: 33.00 in

Barrel Material: Steel or Aluminum

Embedment: 0.00 in

Barrel Manning's n: 0.0240

Inlet Type: Conventional

Inlet Edge Condition: Mitered

Inlet Depression: NONE

Table 3 - Downstream Channel Rating Curve (Crossing: Ex Homewood Creek)

Flow (cfs)	Water Surface Elev (ft)	Depth (ft)	Velocity (ft/s)	Shear (psf)	Froude Number
60.00	6271.19	0.89	5.97	3.21	1.18
94.00	6271.45	1.15	6.95	4.18	1.22
128.00	6271.68	1.38	7.68	4.99	1.25
162.00	6271.88	1.58	8.29	5.72	1.27
196.00	6272.06	1.76	8.80	6.38	1.28
230.00	6272.23	1.93	9.24	6.98	1.30
264.00	6272.39	2.09	9.64	7.55	1.31
298.00	6272.53	2.23	10.00	8.08	1.32
332.00	6272.67	2.37	10.33	8.58	1.33
366.00	6272.80	2.50	10.63	9.06	1.34
370.00	6272.82	2.52	10.66	9.11	1.34

Tailwater Channel Data - Ex Homewood Creek

Tailwater Channel Option: Trapezoidal Channel

Bottom Width: 10.00 ft

Side Slope (H:V): 1.50 (1:1)

Channel Slope: 0.0580

Channel Manning's n: 0.0500

Channel Invert Elevation: 6270.30 ft

Roadway Data for Crossing: Ex Homewood Creek

Roadway Profile Shape: Constant Roadway Elevation

Crest Length: 50.00 ft

Crest Elevation: 6279.00 ft

Roadway Surface: Paved

Roadway Top Width: 40.00 ft